

VC 2300 Projector Mount

Introduction to Functions

GSAT series electric lifting X-type Iron hand, which is used to move down to a suitable height when in use. It is used in hotel banquet halls, exhibition venues, multi-functional conference studios, stages, and large shopping malls. It is used to directly suspend the lights and hide storage the cables and the film and TV after using to maintain the beautiful appearance of the decoration environment. The perfect combination of exquisite craftsmanship and intelligent lift brings a magnificent postmodern visual effect to the application.



- .All-aluminum alloy is refined, beautiful and elegant.
- .X type unique design, 118 ° gear mesh lock, no risk of falling.
- Industrial long running motor, suitable for high frequency and long time use.
- . Wire rope traction, 10 times safety factor.
- .Added independent fall arrester, fall arrest rope, multiple protection.
- .Using digital stroke positioning, repeated operation error is less than 2mm.
- .RF / electric dry contact / RS-485 control mode.
- .The standard power cable X1, category 6 network X1, HDMIX1 are stored in the Iron hand
- .Load capacity <=40kg.
- .Optional color silver / black.









		Maximum size for projector		
Overall dimension(D*W*H)(mm)	Net weight(kg)	(D*W*H)(Line + lens)(mm)	Maximum load(kg)	Rated power(w)
640×320×373	43	730*620*280	40	40
Maximum telescopic stroke(mm)	Lifting accuracy(mm)	noise(dB)	Voltage(v)	jib attachment(mm)
2300	≤1mm	≤55dB	220V/110V	260x752
			Total weight of	
	Angle adjustment	Weakness Dry	package	
Ceiling height(mm)	(Upper/Lower/Level)	Contact(Y/N)	+ product (kg)	Package size (D*W*H)
423	1/8/3/3	√	53	473x420x740
			-	-
Wireless remote control(Y/N)	CAT6 network cable	HDMI 2.0	Power cord	485 Control (Y/N)
N	1	1	1	1

Visbanc

Project Photos







